

**Electrical Package**  
**(Not for habitat)**

**MUST BE SUBMITTED WITH EACH ORDER**

\_\_\_\_\_ \$4,600.00      **Basic Package** (2 light bases, 4 interior plugs, 1 exterior light, 2 light switches, 1 exterior plug, 24 circuit 100Amp 120/240V panel)

**Additional Options**

\_\_\_\_\_ \$60      Light Base

\_\_\_\_\_ \$150      4' LED Strip

\_\_\_\_\_ \$300      8' LED Strip

\_\_\_\_\_ \$300      240V Outlet (Range/Dryer)

\_\_\_\_\_ \$85      Outside Light

\_\_\_\_\_ \$240      Hot Water Tank

\_\_\_\_\_ \$95      Exterior plug

\_\_\_\_\_ \$95      Interior plug or switch (Fridge or Freezer plug)

\_\_\_\_\_ \$55      Dimmer

\_\_\_\_\_ \$120      20A Plug

\_\_\_\_\_ \$600      1000Watt heater Baseboard heater

\_\_\_\_\_ \$900      4000Watt heater Ceiling mounted heater

\_\_\_\_\_ \$370      40Ft 30A 120Volt cord to power building from 30A generator or RV plug

\_\_\_\_\_ \$725      40Ft 50A 120/240Volt cord to power building from 50A generator or RV plug

\$ \_\_\_\_\_ **Total** ( This amount must be added to the options field on the Signed Sales Order )

**Each order must include a signed electrical diagram on ORDER SHEET of sales order.**

-Please specify the height you want the receptacles to be mounted on the Electrical Diagram otherwise they will be mounted at the standard height of 14" to the bottom.

-Outlets/Light bases will be mounted to the nearest stud/rafter.

-All electrical is Approved by Interek.

-Customer is responsible to have a Licensed electrician connect to power.

-Exterior plugs are automatically GFCI. No up-charge.

-Interior plugs are automatically GFCI when within 5' or 1.5 metres from the sink. No up-charge. Sink or future sink must be drawn in the plan to ensure the correct plug is installed.